

1. COMPONENT  ARMY		FY 2011 MILITARY CONSTRUCTION PROJECT DATA			2. DATE 22 APR 2009 22 APR 2009			
3. INSTALLATION AND LOCATION Fort Example CONUS			4. PROJECT TITLE Education Center					
5. PROGRAM ELEMENT		6. CATEGORY CODE 740 25	7. PROJECT NUMBER 78784		8. PROJECT COST (\$000) 6,700			
9. COST ESTIMATES								
ITEM					U/M	QUANTITY	UNIT COST	COST (\$000)
PRIMARY FACILITY								6,068
Education Center					SF	19,800	243.29	(4,817)
IDS Installation					EA	7	144,059	(1,008)
EMCS Connection					LS	--	--	(51)
SDD and EPAct05					LS	--	--	(96)
Antiterrorism Measures					LS	--	--	(96)
SUPPORTING FACILITIES								
ESTIMATED CONTRACT COST								6,068
CONTINGENCY (5.00%)								<u>303</u>
SUBTOTAL								6,371
SUPERVISION, INSPECTION & OVERHEAD (5.70%)								<u>363</u>
TOTAL REQUEST								6,734
TOTAL REQUEST (ROUNDED)								6,700
INSTALLED EQT-OTHER APPROPRIATIONS								(0)
10. Description of Proposed Construction Construct a standard design Education Center for 7,001-10,000 students. Project includes staff areas, classrooms, library space, vocational training shops, laboratories, rehearsal/recording area, information systems, fire protection and alarm systems, Intrusion Detection System (IDS) installation, and Energy Monitoring Control Systems (EMCS) connection. Sustainable Design and Development (SDD) and Energy Policy Act of 2005 (EPAct05) features will be provided. Supporting facilities include site development, utilities and connections, lighting, paving, parking, walks, curbs and gutters, storm drainage, information systems, landscaping and signage. Heating and air conditioning will be provided by (self contained system/connection to the existing energy plant/etc.). Measures in accordance with the Department of Defense (DoD) Minimum Antiterrorism for Buildings standards will be provided. Accessibility for individuals with disabilities will be provided as required. Comprehensive building and furnishings related interior design services are required.								

1. COMPONENT  ARMY	FY 2011 MILITARY CONSTRUCTION PROJECT DATA	2. DATE 22 APR 2009 22 APR 2009
--------------------------	--	---------------------------------------

3. INSTALLATION AND LOCATION  
Fort Example  
CONUS

4. PROJECT TITLE  Education Center	5. PROJECT NUMBER  78784
--	--------------------------------

11. REQ:                    NONE            ADQT:                    NONE            SUBSTD:                    NONE

PROJECT:  
Construct a standard design Education Center for 7,001-10,000 students.

ADDITIONAL:  
The Deputy Assistant Secretary of the Army (Installations and Housing) certifies that this project has been considered for joint use potential. The facility will be available for use by other components.

ESTIMATED CONSTRUCTION START:	MAR 2011	INDEX: 2531
ESTIMATED MIDPOINT OF CONSTRUCTION:	OCT 2011	INDEX: 2556
ESTIMATED CONSTRUCTION COMPLETION:	MAY 2012	INDEX: 2583