

1. COMPONENT Army		FY 2018 MILITARY CONSTRUCTION PROJECT DATA			2. DATE 09 JUN 2016 09 JUN 2016	
3. INSTALLATION AND LOCATION Fort Example CONUS				4. PROJECT TITLE Enhanced Chapel		
5. PROGRAM ELEMENT		6. CATEGORY CODE 730 17	7. PROJECT NUMBER 95843		8. PROJECT COST (\$000) 17,500	
9. COST ESTIMATES						
ITEM				UM	QUANTITY	UNIT COST
PRIMARY FACILITY						
Enhanced Chapel (Medium)				SF	55,000	281.18
Sustainability/Energy Measures				LS	--	--
SUPPORTING FACILITIES						
ESTIMATED CONTRACT COST						15,774
CONTINGENCY (5.00%)						789
SUBTOTAL						16,563
SUPERVISION, INSPECTION & OVERHEAD (5.70%)						944
TOTAL REQUEST						17,507
TOTAL REQUEST (ROUNDED)						17,500
INSTALLED EQT-OTHER APPROPRIATIONS						(0)
10. Description of Proposed Construction Construct a religious facility based upon the Army Standard Design for a Chapel with Worship Center(sanctuary) seating capacity for 400 persons and integral features that allow for expanding that seating to 629 persons by combining the Worship Center and accessory balcony. This facility will include a worship center, activity center with kitchen, multi-purpose areas, baptistery areas, resource center, sacristy area, administrative spaces, information systems, fire protection and alarm systems, Intrusion Detection System (IDS) installation, and Energy Monitoring Control Systems (EMCS) connection. Sustainability and energy enhancement measures are included. Supporting facilities include site development, utilities and connections, lighting, paving, parking, walks, curbs and gutters, storm drainage, information systems, landscaping and signage. Heating and air conditioning will be provided by [self contained system OR connection to the existing energy plant OR etc.]. Measures in accordance with the Department of Defense (DoD) Minimum Antiterrorism for Buildings standards will be provided. Comprehensive building and furnishings related interior design services are required. Access for individuals with disabilities will be provided. Facilities will be designed to a minimum life of 50 years in accordance with DoD's Unified Facilities Code (UFC 1-200-02) including energy efficiencies, building envelope and integrated building systems performance.						
11. REQ:		NONE		ADQT:		NONE
				SUBSTD:		NONE

1. COMPONENT Army	FY 2018 MILITARY CONSTRUCTION PROJECT DATA			2. DATE 09 JUN 2016 09 JUN 2016
3. INSTALLATION AND LOCATION Fort Example CONUS		4. PROJECT TITLE Enhanced Chapel		
5. PROGRAM ELEMENT	6. CATEGORY CODE 730 17	7. PROJECT NUMBER 95843	8. PROJECT COST (\$000) 17,500	
<p>PROJECT: Construct a standard design Chapel Center regular seating capacity up to 400 persons.</p> <p>ADDITIONAL: The Deputy Assistant Secretary of the Army (Installations, Housing and Partnerships) certifies that this project has been considered for joint use potential. The facility will be available for use by other components.</p> <p>ESTIMATED CONSTRUCTION START: MAR 2018 INDEX: 2885 ESTIMATED MIDPOINT OF CONSTRUCTION: OCT 2018 INDEX: 2918 ESTIMATED CONSTRUCTION COMPLETION: MAY 2019 INDEX: 2952</p>				

PREPARATION DATE: 09 JUN 2016 FY 2018 PROGRAM
FORM/PROJECT NUMBER: 95843
PROJECT TITLE: Enhanced Chapel
INSTALLATION: Fort Example
LOCATION: CONUS

GENERAL JUSTIFICATION DATA

Remarks and/or Preparer Notes for Standard Facilities

Besides the basic building costs, some sites on some Installations have soils that require a cost factor to cover the need for special foundation treatments above the average for typical buildings and soils. Consult the Installation DPW office and the CoS P. O. C. for further guidance on this issue.

Some Installations are operating Utility Monitoring and Control Systems (UMCS) and there can be special costs for extending these systems into new facilities. Some sustainable design features that Installations desire to apply to new facilities do require special costs for site support. Consult the Installation DPW office.

Some sites can require special antiterrorism measures that relate to both the building and the site. Consult the Installation DPW office and the CoS P. O. C. for further guidance on this issue. The building information system requirements for this facility type are similar to those required by the typical unspecialized administrative facility.

This facility will require 480Y/277V service for a transformer size of 1,500KVA.

The transformer shall be sized for site conditions. Specific site conditions may require lightning protection and a grounding ring. Communications data and telephone requirements will be governed by I3A and installation requirements. The CoS estimates that 12 Fiber optic cables and 50 copper pair required for this facility.

Cooling, heating, ventilating and air conditioning (HVAC) will be required for the entire facility. The minimum HVAC systems capacities are estimated to be 93.9 tons for cooling and 1293.2 MBH for heating.

The plumbing requirements for this facility include domestic cold and hot water, sanitary waste, gas distribution and fire protection. Domestic cold and hot water should be provided for this facility having a demand of 110 GPM.

The minimum pipe size for domestic water entering the building should be at least 3-inches.

The facility sanitary piping should be sized for approximately 170.5 DFU.

The minimum pipe size leaving the building for sanitary waste should be at least 6-inches.

Fire protection will be required to meet a sprinkler demand of at least 1,280 GPM.

Fire protection service would be served by an 6-inch pipe entering the building.

The maximum gas demand for this building is approximately 1,606 CFH.

Steam or Chilled Water availability varies by site and Installation. Consult the Installation DPW office regarding all utility availability and where multiple sites are being considered, plan the costs according to the site that needs the most development. Paving costs are naturally site dependent. Consult the Installation DPW office and where multiple sites are being considered; plan the costs according to the site that needs the most development.

PREPARATION DATE: 09 JUN 2016 FY 2018 PROGRAM
 FORM/PROJECT NUMBER: 95843
 PROJECT TITLE: Enhanced Chapel
 INSTALLATION: Fort Example
 LOCATION: CONUS

FURNISHINGS AND EQUIPMENT

Furnishings and Equipment

Item	Description	Total Proc Cost Appr Proc (\$000) FY Appr	Est Delivery Date	Proc Status	Est Instl Cost Instl (\$000) FY Instl Appr
1	General Furnishings Footnote: Source of furniture pricing data is the Centralized Furniture Program Office, Huntsville Center (USACE)	438 2017 OMA			
2	Mission Unique Eqp Grp 1 (Misc Eqp Items) Footnote: Source of furniture pricing data is the Centralized Furniture Program Office, Huntsville Center (USACE)	207 2017 OMA			
3	Mission Unique Eqp Grp 2 (Misc Eqp Items) Footnote: Source of furniture pricing data is the Centralized Furniture Program Office, Huntsville Center (USACE)	167 2017 OMA			
4	A/V System Footnote: Source of furniture pricing data is the Centralized Furniture Program Office, Huntsville Center (USACE)	338 2017 OMA			
5	Child Check-In System Footnote: Source of furniture pricing data is the Centralized Furniture Program Office, Huntsville Center (USACE)	10 2017 OMA			

Information Systems Equipment

Item	Description	Total Proc Cost Appr Proc (\$000) FY Appr	Est Delivery Date	Proc Status	Est Instl Cost Instl (\$000) FY Instl Appr
1	Info Sys - ISC	0 2019 OPA			
2	Info Sys - PROP	0 2019			

Totals by Appropriation Type (\$000)

Total OMA/OMN/3400/OM DHP: 1,160
 Installed Equipment - Other Appropriations: 0
 Total Related Furniture & Equipment Amount: 1,160