

1. COMPONENT Army		FY 2018 MILITARY CONSTRUCTION PROJECT DATA		2. DATE 09 JUN 2016 09 JUN 2016	
3. INSTALLATION AND LOCATION Fort Example CONUS			4. PROJECT TITLE Brigade Headquarters		
5. PROGRAM ELEMENT	6. CATEGORY CODE 141 82	7. PROJECT NUMBER 95898	8. PROJECT COST (\$000) 6,400		
9. COST ESTIMATES					
ITEM		UM	QUANTITY	UNIT COST	COST(\$000)
PRIMARY FACILITY					5,749
Brigade Headquarters Building		SF	20,400	276.27	(5,636)
Sustainability/Energy Measures		LS	--	--	(113)
SUPPORTING FACILITIES					
ESTIMATED CONTRACT COST					5,749
CONTINGENCY (5.00%)					287
SUBTOTAL					6,036
SUPERVISION, INSPECTION & OVERHEAD (5.70%)					344
TOTAL REQUEST					6,380
TOTAL REQUEST (ROUNDED)					6,400
INSTALLED EQT-OTHER APPROPRIATIONS					(338)
10. Description of Proposed Construction Construct an extra-small Brigade Headquarters. Primary facilities include administrative operations areas with a Sensitive Compartmented Information Facility (SCIF), Operations Center (OC), and Network Operations Center (NOC). Construction includes redundant mechanical and electrical systems with installation of backup power, secure organizational vehicle parking, and loading service areas, building information systems, fire protection and alarm systems, Intrusion Detection System (IDS) installation, and Energy Monitoring Control Systems (EMCS) connection. Sustainability and energy enhancement measures are included. Supporting facilities include site development, utilities and connections, lighting, paving, parking, walks, curbs and gutters, storm drainage, information systems, landscaping and signage. Heating and air conditioning will be provided by [self contained system OR connection to the existing energy plant OR etc.]. Uninterruptible Power Supply (UPS) will be funded with other appropriations. Measures in accordance with the Department of Defense (DoD) Minimum Antiterrorism for Buildings standards will be provided. Comprehensive building and furnishings related interior design services are required. Access for individuals with disabilities will be provided. Facilities will be designed to a minimum life of 50 years in accordance with DoD's Unified Facilities Code (UFC 1-200-02) including energy efficiencies, building envelope and integrated building systems performance.					

1. COMPONENT Army	FY 2018 MILITARY CONSTRUCTION PROJECT DATA			2. DATE 09 JUN 2016 09 JUN 2016
3. INSTALLATION AND LOCATION Fort Example CONUS		4. PROJECT TITLE Brigade Headquarters		
5. PROGRAM ELEMENT	6. CATEGORY CODE 141 82	7. PROJECT NUMBER 95898	8. PROJECT COST (\$000) 6,400	
11. REQ: NONE ADQT: NONE SUBSTD: NONE PROJECT: Construct an extra-small Brigade Headquarters. ADDITIONAL: The Deputy Assistant Secretary of the Army (Installations, Housing and Partnerships) certifies that this project has been considered for joint use potential. The facility will be available for use by other components. ESTIMATED CONSTRUCTION START: MAR 2018 INDEX: 2885 ESTIMATED MIDPOINT OF CONSTRUCTION: OCT 2018 INDEX: 2918 ESTIMATED CONSTRUCTION COMPLETION: MAY 2019 INDEX: 2952				

PREPARATION DATE: 09 JUN 2016 FY 2018 PROGRAM
FORM/PROJECT NUMBER: 95898
PROJECT TITLE: Brigade Headquarters
INSTALLATION: Fort Example
LOCATION: CONUS

GENERAL JUSTIFICATION DATA

Criteria for Proposed Construction

Project scope includes an extra-small Brigade HQ with {__?__} staff. The Standard Requirements Code(SRC) and or Unit Identification Code(UIC) for the using activity to occupy this facility is {__?__}.

PREPARATION DATE: 09 JUN 2016 FY 2018 PROGRAM
 FORM/PROJECT NUMBER: 95898
 PROJECT TITLE: Brigade Headquarters
 INSTALLATION: Fort Example
 LOCATION: CONUS

FURNISHINGS AND EQUIPMENT

Furnishings and Equipment

Item	Description	Total Proc Cost Appr Proc (\$000) FY Appr	Est Delivery Date	Proc Status	Est Instl Cost Instl (\$000) FY	Instl Appr
1	Bde Furniture	620 2019	OMA			
	Footnote:					
	Source of furniture pricing data is the Center of Standardization for this facility type					
2	Bde Equipment	338 2019	OPA			
	Footnote:					
	Source of equipment pricing data is the Center of Standardization for this facility type					

Information Systems Equipment

Item	Description	Total Proc Cost Appr Proc (\$000) FY Appr	Est Delivery Date	Proc Status	Est Instl Cost Instl (\$000) FY	Instl Appr
1	Info Sys - ISC	0 2019	OPA			
2	Info Sys - PROP	0 2019				

Totals by Appropriation Type (\$000)
 Total OMA/OMN/3400/OM DHP: 620
 Installed Equipment - Other Appropriations: 338
 Total Related Furniture & Equipment Amount: 958